

Bridging the Gap: Collaborating Our Way into the Future

Alison Macken-Allen Nitika Bothra

Auckland Transport



Alison Macken-Allen | LinkedIn



Nitika Bothra | LinkedIn







Auckland Transport's Bridge Journey



Current State

- Challenging the status quo of asset data
- Creating data and infrastructure resilience




Unlocking Potential

- AMDS
- Data hierarchy
- BIM Model



Future Outlook

- Auckland Transport's journey forward












Why Bridges... and why now



Mill Flat Road Bridge








Bridge Kerb

→•□□








Bridge Deck

▶• ■ Bridge Superstructure

ud_br_superstructure

Unlocking Potential

Evolution of Bridge Hierarchy – From Silos to Synergy







Asset Life

Construction Date

Alpha 🗘 🛈 🕢 GM Unlocking Potential thinkproject RAMM AT Bridges ∨ Bridge Deck #1097 - Prestressed Concrete OBB = 용 Tags > Draft Add |% | IF There is no media for this item. AMDS w Material **Dimensions** \blacksquare Overall Width Kerb Height Thickness General D1 Deck Prestressed Concrete Type Deck Gradient Type Unknown 1/1 Notes * Draft Approval Status






27/02/2013



Overcoming Obstacles with Key Solutions









Maintaining Quality and Fostering Maturity


BRIDGE 2 score:95.29

BRIDGE2

Bridges valid

The percentage of AT bridge records with valid dimensions (length, width) and condition date (when recorded) >= install/constructed date

Gauge of complete bridges over total bridges




Metric Purpose


Confirm completeness of Bridge assets attribute data is adequate for planning and decision-making purposes.

Consequence of Poor Quality Data

Poor data has the potential to impact our renewal programme development, investment decision making, asset valuations and LoS delivery.



invalid date, Length is 0, Width is 0, Count of Start for 0, Count of End for 0 and Start less than or equal to end







Maintaining Quality and Fostering Maturity

BRIDGE3 score is: 82.71

BRIDGE3

Bridge assets known

-- -----

The percentage of the number of Bridge records with a known type, asset owner/manager, location (start and end), displacement and side or map coordinates), condition, and constructed/installation date.

Gauge of complete bridges out of total bridges




Metric Purpose


Confirm completeness of Bridge assets attribute data is adequate for planning and decision-making purposes.

Consequence of Poor Quality Data

Poor data has the potential to impact our renewal programme development, investment decision making, asset valuations and LoS delivery.

Asset ID	Name	Condition	Road
1461	(ABERDEEN/BLUEWATER PL)/CREEK	Unknown	BLUEWATER PL / ABERDEEN CRES CYWA
1481	(ORUARANGI RD/BEACH RD) 1	Unknown	OTAUTAUA STONEFIELDS CYWAY
1482	(ORUARANGI RD/BEACH RD) 2	Unknown	OTAUTAUA STONEFIELDS CYWAY
1483	(ORUARANGI RD/BEACH RD) 3	Unknown	OTAUTAUA STONEFIELDS CYWAY
1484	(ORUARANGI RD/BEACH RD) 4	Unknown	OTAUTAUA STONEFIELDS CYWAY
1585	524 GREAT SOUTH RD PED BRIDGE	Unknown	GREAT SOUTH RD (PAPAKURA)
1390	ABBOTTS/GRAND #1	Unknown	ABBOTTS WAY / GRAND DR CYWAY
1391	ABBOTTS/GRAND #2	Unknown	ABBOTTS WAY / GRAND DR CYWAY
1459	ABERDEEN/BLUEWATER PL	Unknown	BLUEWATER PL / ABERDEEN CRES CYWA
1460	ABERDEEN/BLUEWATER PL LAKE	Unknown	WATTLE DOWNS ESP RESERVE LAKE CY
1294	ABERLEY-PIN OAK	Good	PIN OAK DR/ABERLEY RD CYWAY









Future Outlook

Where to next?

S6 Bridge Inspection Report

Auditing and Vesting Handover

Bridge general inspection report - page 1 of 2

NZ TRANSPORT AGENCY WATA KOTAHI			Bridge general inspection report			Supplier logo				
Network area:			Bridge name:		Highwa	y:	RP:	BSN:		
Bridge type:			Superstructure material:					·		
Year constructed:			Deck material:							
Marking code			Deck width:		Map ref. (easting):					
0 = Not inspected 1 = Satisfactory			Total bridge length:			Map ref.	(northing):			
2 = Monitor next inspection (provide comment & photo)			No. of spans:			Owner:				
S = Structural maintenance (provide comment & photo)				oan lengths (m):		RCA:				
N = Not applicable			Next inspection type:			ļ		spection type:		
Date:		Next inspection date:			Previous inspect		spection date	:		
E	leme	nt		Mork	Drief deserie	tion of de	foot one	Laammani	in.	1
Set	No	Description	n	Wark	Brief descrip	otion of de	erect and	commen	ıs	
	1	Primary load	carrying element							
e l	2	Secondary	Transverse beams							
Superstructure elements	3	element(s)	Other (incl. deck)							
perstructi elements	4	Half joints								
per	5	Seismic linkages/holding down bolts								
ng.	6	Parapet beam or cantilever								
	7	Cross bracing								
	8	Foundations								
_ [9	Abutments								
ure Ture	10	Head wall								
ruc	11	Pier / column								
Load-bearing substructure	12	Cross-head /	capping beam							
	13	Bearings								
	14	Bearing plinth	/ shelf							
st	15	Superstructu	re drainage							



Thank you to...

- Gang Yu (Principal Asset Engineer) and the AT Asset Management team
- Richard Gale, Glenn Manley & the ThinkProject team
- Mary Tan, Adhi Krishnamoorthy and Adarsh Narangoli (AT Asset Information Bridges Project Team)
- AMDS team





Nga mihi

Thank you!



Alison Macken-Allen | LinkedIn



Nitika Bothra | LinkedIn



